

ORIGINAL

SIDE ONE


STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
RECOMPLETION FORM
ACO-2 AMENDMENT TO WELL HISTORY

Operator: License # 5447Name: OXY USA, Inc.Address: P.O. BOX 26100City/State/Zip: OKLA. CITY, OK 73126-0100Purchaser: NNOperator Contact Person: Raymond Hui
Phone: (405) 749-2471Designate Type of Original Completion
 New Well Re-Entry X WorkoverDate of Original Completion 9-8-75Name of Original Operator OXY USA, Inc.Original Well Name Brown C #3Date of Recompletion: 10-31-90 4-2-91Commenced 10-31-90 Completed 4-2-91Re-entry ☐ Workover ☒Designate Type of Recompletion/Workover:
 X Oil SWD Temp. Abd.
 X Gas X Inj Delayed Comp.
 Dry Other (Core, Water Supply, etc.) X Deepening Re-perforation
 X Plug Back 6070 PBD
 Conversion to Injection/Disposal

Is recompleted production:

 Commingled Docket No.
 Dual Completion Docket No.
 X Other (Disposal or Injection?) Docket No. #26113API NO. 15- 175-20262-00-01County Seward CW/2 SE Sec. 17 Twp. 34S Rge. 33 X East West1320 Ft. North from Southeast Corner of Section1980 Ft. West from Southeast Corner of Section

(NOTE: Locate well in section plat below.)

Lease Name Brown C Well # 3Field Name SalleyProducing Formation Toronto (Producing zone)
Morrow (Inj. Zone)Elevation: Ground 2861 KB 2869

K.C.C. OFFICE USE ONLY

F Letter of Confidentiality Attached
C Wireline Log Received
C Drillers Timelog Received

Distribution

 X KCC SWD/Rep NGPA
 KGS Plug Other
(Specify)

INSTRUCTIONS: This form shall be completed in triplicate and filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 120 days of the recompletion of any well. Rules 82-3-107 and 82-3-141 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107 for confidentiality in excess of 12 months. One copy of any additional wireline logs and driller's time logs (not previously submitted) shall be attached with this form. Submit ACO-4 or ACO-5 prior to or with this form for approval of commingling or dual completions. Submit CP-1 with all plugged wells. Submit CP-111 with all temporarily abandoned wells. NOTE: Conversion of wells to either disposal or injection must receive approval before use; submit form U-1.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature Vic Tumlinson Title Operations Drilling Manager Date 4-2-91Subscribed and sworn to before me this 2nd day of April 19 91Notary Public Lay Ann Kilmer Date Commission Expires 4-16-94

SIDE TWO

Operator Name OXY USA, Inc. Lease Name Brown C Well # 3
 Sec. 17 Twp. 34S Rge. 33 ☐ East ☒ West
 County Seward

RECOMPLETION FORMATION DESCRIPTION

No new ele. logs have been run ☐ Log ☐ Sample

Name	Top	Bottom
Toronto	4328'	4335'
Morrow	6036	6048
TD		6605
PBTD		6078

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose:	Depth		Type of Cement	# Sacks Used	Type and Percent Additives
	Top	Bottom			
<input type="checkbox"/> Perforate					
<input type="checkbox"/> Protect Casing					
<input checked="" type="checkbox"/> Plug Back TD	4328	6048	Set CIBP at	6000'; dumped	2 sx of cmt on top of CIBP. Perf. @ 4650'
<input type="checkbox"/> Plug Off Zone			w/4 shots for squeeze.	Pumped 100 sx Cl.H cmt.	Squeezed w/195 sx cmt.
			Perf. @ 4390'	w/4 shots. Pumped 100 sx Cl.H	Squeezed w/85 sx. Perf.
			@ 4285'. Pumped 100 sx Cl.H.	Squeezed w/85 sx.	

Shots Per Foot	PERFORATION RECORD	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)
	Specify Footage of Each Interval Perforated	
4	Toronto 4328-4335	Not Treated.
	(7'; 28 shots)	

PBTD 6070' Plug Type CIBP

TUBING RECORD

Size 2 7/8" Set At 6000' Packer At 6000' Was Liner Run ☒ ☐ N

Date of Resumed Production, Disposal or Injection 12-4-90

Estimated Production Per 24 Hours Oil X Bbls. Water - Bbls. - Gas-Oil-Ratio

Gas 135 Mcf

Disposition of Gas:

☐ Vented ☐ Sold ☐ Used on Lease (If vented, submit ACO-18.)