

15-189-00167-0000

1060190

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 9/25/49
C S/2 S/2
NW/4, SEC. 14, T 31 S, R. 35 W/E

2310 feet from N/E section line

1320 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name Carrie Winter Well # 1

Operator: Mobil Oil Corporation

County Stevens

Name &

Address P. O. Box 5444

Well Total Depth 2820 91.65 feet

Denver, CO 80217

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 650

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 10:00 am Day: 28 Month: February Year: 19 84

Plugging proposal received from Ed Eaves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 7" Production Pipe at 2819'

1st plug set packer on tubing at 1425' and pump 4 sx hulls, 33 sx cement, & 28 barrels

of mud and 65 sx cement through tubing. Pull tubing and packer out of hole.

2nd plug set CBP at 1390' with 5 sx cement on top.

3rd plug run tubing to top of cement and fill casing with heavy mud. Pull tubing to 1250'
and spot 50 sx cement. 4th plug pull tubing to 700' and spot 42 sx cement. 5th plug at 50'
cement to surface with 10 sx Plugging Proposal Received by Paul A. Luthie
cement. (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None _____ X

Operations Completed: Hour: 4:30 pm Day: 1 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug set packer on tubing at 1425' and pump 4 sx hulls, 33 sx

cement, 28 barrels mud and 65 sx cement through tubing. Pull tubing and packer out of

hole. 2nd plug set CBP at 1390' with 5 sx cement on top. 3rd plug run tubing on top of

cement and fill casing with heavy mud. Pull tubing to 1250' and spot 50 sx cement. 4th

plug pull tubing to 700' and spot 42 sx cement. 5th plug at 50' -- cement to surface

with 10 sx cement.

Remarks: Used common sack cement. No recovery by Midwest Casing Pulling

(if additional description is necessary, use BACK of this form.)

RECEIVED

STATE CORPORATION COMMISSION

INVOICED

DATE 3-12-84

MAR 07 1984

Signed Paul A. Luthie
(TECHNICIAN)

INV. NO. 0679 3-1

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84