

1 020085

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-21,051-0000
SW NW, SEC. 14, T 31 S, R 35 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208
Operator: Mobil Oil Corporation
Name & Address P.O. Box 5444
Denver, CO 80217

Lease Name Simon Winter Well # 1
County Stevens 188.34
Well Total Depth 5795 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1799

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling Inc. License Number 5382

Address Box 916, Garden City, KS 67846

Company to plug at: Hour: 7:15 p.m. Day: 4 Month: 7 Year: 1987

Plugging proposal received from Jack Pepper

(company name) Cheyenne Drilling Inc. (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2990'

1st plug at 3157' with 100 sx cement, 2nd plug at 2693' with 100 sx cement,
3rd plug at 1796' with 50 sx cement, 4th plug at 809' with 50 sx cement,
5th plug at 0-50' with 16 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10 p.m. Day: 4 Month: 7 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 3157' with 100 sx cement, STATE CORPORATION COMMISSION

2nd plug at 2693' with 100 sx cement,
3rd plug at 1796' with 50 sx cement,
4th plug at 809' with 50 sx cement,
5th plug at 0-50' with 16 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

RECEIVED
JUL 7 1987
7-7-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used Class H cement w/2% cc by Western.

(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 7-7-87

Signed Glenn R. Barlow
(TECHNICIAN)

INV. NO. 17438

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date May 15, 1987
 month day year
 License # 5208
 OPERATOR: Mobil Oil Corporation
 Name P.O. Box 5444
 Address Denver, Colorado 80217
 City/State/Zip J. L. Douglass
 Contact Person (303) 298-2047
 Phone

API Number 15- 189-21,051-0000
 SW NW Sec. 14 Twp. 31 S, Rg. 35 West
3300 Ft. from South Line of Section
4620 Ft. from East Line of Section
 (Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License #
 Name Cheyenne
 City/State
 Well Drilled For: Oil SWD Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 670 feet
 County Stevens
 Lease Name Simon Winter Well # 1
 Ground surface elevation 2990 feet MSL
 Domestic well within 330 feet: yes no
 Municipal well within one mile: yes no
 Depth to bottom of fresh water 575 520
 Depth to bottom of usable water 600
 Surface pipe by Alternate: 1 2
 Surface pipe planned to be set 625
 Conductor pipe required NONE
 Projected Total Depth 6000 feet
 Formation Chester

If OWWO: old well info as follows:
 Operator
 Well Name
 Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
 Date 4/24/87 Signature of Operator or Agent J. L. Douglass for J.L.D. Title Reg. Compliance Manager

For KCC Use:
 Conductor Pipe Required _____ feet; Minimum Surface Pipe Required _____ feet per Alt. 1
 This Authorization Expires 6-27-87 Approved By J. L. Douglass

Move in 6-23-87 set 1800'

SW NW Sec. 14 Twp. 31 S, Rg. 35 East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ <u>3200</u>	feet depth with <u>40</u>	sxs of <u>Class. H. Cmt. w/3% CaCl₂</u>
2nd plug @ <u>2900</u>	feet depth with <u>40</u>	sxs of <u>" " "</u>
3rd plug @ <u>2600</u>	feet depth with <u>40</u>	sxs of <u>" " "</u>
4th plug @ <u>(Btm Surf. Csg. = 75')</u>	feet depth with <u>75</u>	sxs of <u>" " "</u>
5th plug @ <u>600</u>	feet depth with <u>50</u>	sxs of <u>" " "</u>
(2) Rathole with <u>20</u>	sxs	(b) Mousehole with <u>20</u> sxs
6th plus @ <u>40</u>	feet depth with <u>14</u>	sxs of <u>" " "</u>

PUSHER Jack Pepper
 TD 5795 FORMATION
 SURFACE PIPE 8 5/8 @ 1799
 ANHYDRITE ELEVATION 2990
 STARTING TIME & DATE 7:15 pm 7-4
 COMPLETION TIME & DATE 10 pm
 1st PLUG @ 3157 FT. W/ 100 SX
 2nd PLUG @ 2693 FT. W/ 100 SX
 3rd PLUG @ 1796 FT. W/ 50 SX
 4th PLUG @ 809 FT. W/ 50 SX
5th RAT HOLE CIRCULATED W/ 15 SX
 MOUSE HOLE CIRCULATED W/ 10 SX
 WATER WELL PLUGGED W/ _____ SX
 CEMENT COMPANY Western Chemt
 TECHNICIAN Alan Saw

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 7 1987
 CONSERVATION DIVISION
 Wichita, Kansas

plug