

To: 1 020431
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-22 API NUMBER 15- 189-21,479-0000 1160

SW, SEC. 15, T. 31 S, R. 35 W/E
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208
Operator: Mobil Oil Corp.
Name & Address: 2319 N. Kansas
Liberal, KS 67901

Lease Name E.L. Gaskill Unit Well # 1-4
County Stevens 99.17
Well Total Depth 2990 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 613

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling Service License Number 6497
Address 506 Ellis, Sublette, KS

Company to plug at: Hour: 11 a.m. Day: 22 Month: 1 Year: 19 92

Plugging proposal received from Ed Eves
(company name) Midwest Casing Pulling Service (phone) 316-675-8349

were: 5 1/2" at 2989' w/460 sx cement, Perfs at 2674-2850'
1st plug fill 5 1/2" with cement,
2nd plug tie onto 8 5/8" X 5 1/2" and pump.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3:30 p.m. Day: 22 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 5 sx hulls and 200 sx cement down 5 1/2", pressured up to 150 psi. Let set for two hours. Pipe full.
2nd plug pumped down 8 5/8" X 5 1/2" annulus. Pressured to 450 psi. Filled to surface with approximately 20 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 28 1992

Remarks: Used common cement by Midwest. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

DATE 1-29-92
INV. NO. 34412

Signed Glen R. Barlow
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 7/16/88 month day year

API Number 15-189-21,223-0000

OPERATOR: License # 5208
Name Mobil Oil Corporation
Address P. O. Box 5444
City/State/Zip Denver, CO 80217
Contact Person B. R. Maynard
Phone (303) 298-2069

NE SE Sec. 15 Twp. 31 S, Rg. 35
2130 Ft. from South Line of Section
660 Ft. from East Line of Section
256-4346 5500 (Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 510 feet

CONTRACTOR: License # Contractor not selected.
Name Will advise on ACO-1.
City/State
Well Drilled For: Oil SWD Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Lease Name Churchman Bible Well # 4
Ground surface elevation 2994 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water 575
Depth to bottom of usable water 600 (620)
Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 625
Conductor pipe required None
Projected Total Depth 5900 feet
Formation Chester, St. Louis

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 7/1/88 Signature of Operator or Agent B. R. Maynard Title Regulatory Compliance Mgr

For KCC Use:
Conductor Pipe Required 1-5-88 feet; Minimum Surface Pipe Required 640 feet per Alt. 1 X
This Authorization Expires 7-5-88 Approved By P.H. 7-5-88

EFFECTIVE DATE: 7-10-88

mobil Spud 9-23-88

Set 1860' 8 1/2" SD.
NE SE Sec. 15 Twp. 31 S, Rg. 35 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, feet depth with, and Class H Cmt w/3% CaCl2. Includes rows for 1st through 6th plugs and Rathole.

NOTE:

Handwritten notes including: Waller Halt, Jim Amundson, TD 5900 FORMATION, SURFACE PIPE 8 1/2" @ 1830' 6 1/2" SX, ANHYDRITE ELEVATION 9-29-88, STARTING TIME & DATE 1:00 AM, COMPLETION TIME & DATE 9-29-88 3:30 AM, 1st PLUG @ 3191 FT. W/ 40 SX, 2nd PLUG @ 2990 FT. W/ 40 SX, 3rd PLUG @ 2660 FT. W/ 40 SX, 4th PLUG @ 1980 FT. W/ 60 SX, 5th PLUG @ 1780 FT. W/ 50 SX, RAT HOLE CIRCULATED W/ 40 SX, MOUSE HOLE CIRCULATED W/ 15 SX, WATER WELL PLUGGED W/ 10 SX, CEMENT COMPANY Houston Western

TECHNICIAN
STATES RECEIVED
CORPORATION COMMISSION
OCT 12 1988
CONSERVATION DIVISION
Wichita, Kansas