

2 100434

11-22

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 191-20,890-0000

C N/2 NE, SEC. 29, T 30 S, R 2 WXR

feet from S section line

feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6044

Lease Name Jordon Trust Well # 1

Operator: Stelbar Oil Corp.

County Sumner 93.93

Name & Address 450 Fourth Financial Cntr.

Well Total Depth 2890' PB 2850' feet

Wichita, KS 67202

XXXXXX Pipe: Size 4-1/2" feet 2889'/130 SX

316-264-8378

Surface Casing: Size 8-5/8" feet 269'/175 SX

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated perf 2812' - 2814'

Plugging Contractor B&S Well Service License Number 6013

Address Box 837, Winfield, KS

Company to plug at: Hour: 11:00 Day: 22 Month: 11 Year: 1988

Plugging proposal received from Marty Shawver

(company name) Stelbar Oil Corp. (phone) 316-264-8378

work: Fill hole to 50' above top perf w/chat & dump 4 sx cement w/bailer - shoot & pull pipe to 300' & circulate to surface.

Plugging Proposal Received by Merlan Unruh (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:00p Day: 22 Month: 11 Year: 1988

ACTUAL PLUGGING REPORT: Filled w/chat to 2760' & dumped 5 sx cement w/bailer - shot & pulled 2224' of 4-1/2" pipe to 400' & circulated 2 sx of hulls & 200 sx of cement - pulled pipe and tagged cement at 40' & filled to top w/redi mix.

STATE CORPORATION COMMISSION

DEC 9 1988

1-8-88 CONSERVATION DIVISION Wichita, Kansas

Remarks: United #3028 60/40 2% gel 2 sx hulls (If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 9 1988

INV. NO. 23302

Handwritten signature/initials

Signed Johnny C. Sanders (TECHNICIAN)