

2 070091

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 191-21,849-0000  
NESESW, SEC. 25, T 30 S, R 2 W/EX  
990 feet from N/S section line  
2980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5038

Lease Name Bates A Well # 1

Operator: Robinson Oil Company

County Sumner 123.83

Name & Address 737 R.H. Garvey Bldg.

Well Total Depth 3810 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 12 1/4 feet 514

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor RRA, Inc. License Number 5656

Address Wichita, KS

Company to plug at: Hour: Day: 10 Month: 8 Year: 19 85

Plugging proposal received from

(company name) (phone)

were: Circulate: 35 sacks at 1250 feet; 35 sacks at 550 feet; 25 sacks at 60 feet;  
10 sacks in rat hole

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:45p. Day: 10 Month: 8 Year: 19 85

ACTUAL PLUGGING REPORT Conditioned hole with mud, ran drill pipe to 1250 feet and  
circulated 35 sacks of cement. Pulled pipe to 550 feet and circulated 35 sacks  
of cement. Pulled pipe and ran wood plug to 60 feet and circulated 25 sacks of  
cement to surface. Circulated 10 sacks of cement in rat hole.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Sun #283600

AUG 16 1985

(If additional description is necessary, use BACK of this form.)

(SEE) (SEE) (SEE) observe this plugging.

CONSERVATION DIVISION Wichita, Kansas

INVOICED  
DATE AUG 19 1985  
INV. NO. 9654  
P-70

Signed [Signature] (TECHNICIAN)

Starting Date: July 25 1985  
month day year

OPERATOR: License # 5038  
Name Robinson Oil Company  
Address 737 R. H. Garvey Bldg.  
City/State/Zip Wichita, KS 67202-2992  
Contact Person Dale M. Robinson  
Phone (316) 262-6734

CONTRACTOR: License # 5656  
Name R.R.A., Inc.  
City/State Wichita, KS

Well Drilled For:	Well Class:	Type Equipment:
<input checked="" type="checkbox"/> Oil <input type="checkbox"/> Swd <input type="checkbox"/> Infield <input checked="" type="checkbox"/> Mud Rotary		
<input type="checkbox"/> Gas <input type="checkbox"/> Inj <input checked="" type="checkbox"/> Pool Ext. <input type="checkbox"/> Air Rotary		
<input type="checkbox"/> OWWO <input type="checkbox"/> Expl <input type="checkbox"/> Wildcat <input type="checkbox"/> Cable		

If OWWO: old well info as follows:  
Operator .....  
Well Name .....  
Comp Date ..... Old Total Depth .....  
Projected Total Depth 3800 ..... feet  
Projected Formation at TD Mississippian .....  
Expected Producing Formations Kansas City, Miss. ....

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging holes to K.C.C. specifications.

Date 7-25-85 ..... Signature of Operator or Agent *Dale M. Robinson* Title Owner

API Number 15-191-21,849  
NE SE SW  
(location) 100000

990 ..... Ft North from Southeast Corner of Section  
2980 ..... Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 ..... feet.  
County Sumner .....  
Lease Name Bates "A" ..... Well# 1 .....  
Domestic well within 330 feet:     yes     no  
Municipal well within one mile:     yes     no

Depth to Bottom of fresh water ..... 50 ..... feet  
Lowest usable water formation Wellington .....  
Depth to Bottom of usable water 250 ..... feet  
Surface pipe by Alternate:    1     2   
Surface pipe to be set 450 ..... feet  
Conductor pipe if any required None ..... feet  
Ground surface elevation 1330 ..... feet MSI.  
This Authorization Expires 1-25-86  
Approved By RCH 7-25-85