

2 040397

3-16-88 15-191-00428-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- OWWO 2-10-79

SE SE SE, SEC. 20, T 30 S, R 2 W/XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 3646

330 feet from S section line

Operator: Haven Energy Corporation

330 feet from E section line

Name: Haven Energy Corporation

Lease Name Rein Beck Well # 1

Address 7310 E. Kellogg

County Sumner 104.72

Well Total Depth 3222 feet

Wichita, KS 67207

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 150

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B & S Well Service License Number 6012

Address Winfield, KS 67156

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Bobby

(company name) B & S Well Service (phone)

were: 4 1/2" @2980 2871-76 Perf Run flag to TD, Pump 59 sxs on bottom.

Squeeze top 3 hulls, 10 gel, 70 sxs Howco Lite

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 18:30 Day: 16 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT The well would flow gas and saltwater, therefore a 50 sxs plug

was pumped to app. 2000'. The 4 1/2" was shot off at 1892' and recovered. The

top was squeeze plugged through a 2" collar by pumping 2 1/2 sxs of hull.,

10 sxs gel, 1/2 sxs hulls, and 70 sxs Halliburton Lite Cement.

MAR 21 1988

Remarks: Howco Max 350# Shut In 200#

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 3-25-88

Signed [Signature] (TECHNICIAN)

INV. NO. 20195

CUSTOMER: HAVEN ENERGY CORP. WELL NAME: REIN/BECK #1; SE/4 SEC.20,T30S,R2W
(SANDERS OIL CO.)

PIPE SIZE: 8-5/8" @ 150' #1)% EXCESS: EST FT FILL:
HOLE SIZE: 7-7/8" #2)% EXCESS: EST FT FILL:

HALLIBURTON SERVICES'

CEMENTING PRICES -----WINFIELD, KS----- 16-Mar-88

70 SKS CEMENT BLEND #1 SLURRY WT. 13.08 #/GAL
HLC W/2% ADDL. GEL SLURRY YIELD 1.92 CU. FT./SI
WATER REQ'D 9.99 GALLONS

PERCENT MATERIAL	POUNDS	PRICE
70 SKS HALLIBURTON LIGHT	6454	337.40
2 % GEL(ADD. HLC 1-4%)	122	25.90
10 SKS GEL		63.00
3 SKS HULLS	0	36.00

MAT'L COST---BLEND #1		\$462.30
MAT'L COST---BLEND #2		0.00
50 MI. DRAYAGE	164.40 TON-MILES	115.08
SERV. CHG.(NO ENTRY)	.72.03 CU. FT.	68.43

CEMENTING MATERIALS COST =====> \$645.81

UNITS	DESCRIPTION	PRICE
50 MI.	MILEAGE	\$105.00
1	PLUG TO ABD., SPEC. KS	370.00
1	-8 5/8" CMT PLUG,WOOD	54.00
	PUMPING SERVICE COST=====>	\$529.00

UNITS	DESCRIPTION	PRICE
-------	-------------	-------

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1988

CONSERVATION DIVISION
Wichita, Kansas

SUMMARY:	LIST	DISC	NET
MATERIALS COST=====>	\$645.81	25.0	\$484.35
PUMPING SERVICE COST=====>	529.00		529.00
SALES PRODUCTS COST=====>	0.00		0.00

REMI BECK

TOTAL CEMENTING COST=====> \$1,174.81

13.7%

\$1,013.35

-tax 38.65

\$1,052.00

pd 3/16/88
CK# 157

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1988

CONSERVATION DIVISION
Wichita, Kansas