

1 060536

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,336-A-0001

C SE SW, SEC. 18, T 33 S, R 29 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7265

Lease Name Burmeister Well # 1

Operator: R. H. Siegfried, Inc.

County Meade 153.56

Name & Address 1924 S. Utica, Suite 1120

Well Total Depth 4725 feet

Tulsa, OK 74104

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1537 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9:00 am Day: 9 Month: April Year: 19 85

Plugging proposal received from Don Horton

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" set at 4725' Perfs at 4591-4601'

1st plug pump 2 sx hulls and 25 sx cement to bottom

pump through 5 1/2" with heavy mud between plugs

2nd plug at 1560' with 50 sx cement

3rd plug at 680' with 25 sx cement
solid bridge

4th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthi
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None

Operations Completed: Hour: 11:00 am Day: 9 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to bottom, 2nd plug
at 1560' with 50 sx cement, 3rd plug at 680' with 25 sx cement, 4th & 5th plugs - solid
bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 12 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2610' 5 1/2" casing. Used Common sacked cement by Sargent's
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

Signed Paul A. Luthi (TECHNICIAN) SD

DATE 4-18-85

INV. NO. 7778