

To: 1 020705  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200, COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-8

API NUMBER <sup>-119-</sup> 15-01,004-~~0000~~ <sup>00-01</sup>  
C NE NW, SEC. 18, T. 33 S, R. 29 W/EX  
4620 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255  
Operator: McGinness Oil Company  
Name & Address: 1026 Union Ctr. Bldg.  
Wichita, KS 67202

Lease Name Condry Well # 1  
County Meade 205.56  
Well Total Depth 6325 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 9 5/8 feet 1523

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 9 a.m. Day: 7 Month: 9 Year: 1993

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

Work: 4 1/2" at 5223' w/300 sx cement, PBTD 4860', Perfs at 4819-24'  
1st plug pump 1 sx hulls and 20 sx cement at perfs, displace with mud, pressure up,  
2nd plug pump 50 sx cement at 1560', displace with mud,  
3rd plug pump 40. sx cement at 650', 4th plug pump 10 sx cement at 35 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 2:30 p.m. Day: 8 Month: 9 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs,  
displaced with mud, pressured up,  
2nd plug pumped 50 sx cement at 1560', displaced with mud,  
3rd plug pumped 40 sx cement at 650',  
4th plug pumped 10 sx cement at 35 to -4'.

Remarks: Used common cement by Sargent & Horton Plugging. Recovered 2739' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE SEP 21 1993

Signed Glenn R Barlow (TECHNICIAN)

INV. NO. 38727 NOV 15 1993

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 15 1993  
CONSERVATION DIVISION  
Wichita, Kansas