

1 050387

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 119-20,645 - 0000

SE/4, SEC. 25; T. 33 S, R 29 W/E

2310 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6731

Lease Name Eckhoff Well # 1

Operator: Deck Oil Company

County Meade 188.66

Name & Address 2300 One Williams Center

Well Total Depth 5805 feet

Tulsa, OK 74172

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1606

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: noon Day: 26 Month: November Year: 19 84

Plugging proposal received from Ed Eaves

(company name) Midwest (phone) 316-675-8349

were: 4 1/2" set at 5805 PBD 5648 Perfs at 5630-5638

1st plug pump 2 sx hulls and 20 sx cement to bottom

2nd plug at 1650' with 40 sx cement

3rd plug at 800' with 30 sx cement  
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 2:00 pm Day: 26 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 5805' PBD 5648' Perfs at 5630-5638'

1st plug pumped 2 sx hulls and 20 sx cement to bottom, 2nd plug at 1650' with 40 sx

cement, 3rd plug at 800' with 30 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement.

Remarks: Used common sacked cement by Midwest

(If additional description is necessary, use BACK of this form.)

I (~~xxx~~ did not) observe this plugging.

12-3-84

Signed Richard W. Lacey  
(TECHNICIAN)

5732