

1 110172

API NUMBER 15-Drilled 7/9/58

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE SE, SEC. 26, T 33 S, R 29 W/EX

530 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9183

Lease Name Ed Eckhoff Well # 1

Operator: Bentley & Laing

County Meade 187.36

Name &

Address P.O. Box 294

Well Total Depth 5765 feet

Wichita Falls, TX 76307

Conductor Pipe: Size feet

Surface Casing: Size 9 5/8 feet 1511

Abandoned Oil Well Gas Well ☒ Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: Day: 27 Month: 12 Year: 19 90

Plugging proposal received from Bob Sargent

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 5765' w/125 sx cement, Perfs at 5624-76'

1st plug pump 25 sx cement to bottom,

2nd plug at 1530' with 50 sx cement,

3rd plug at 700' with 50 sx cement,

4th plug at 40' with 15 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None ☒

Operations Completed: Hour: Day: 2 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement from 5676-5500',

2nd plug pumped 50 sx cement from 1540-1440',

3rd plug pumped 50 sx cement from 700-600',

4th plug pumped 15 sx cement from 40-0'.

RECEIVED
STATE CORPORATION COMMISSION

APR 02 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2629' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(XXX) (if not) observe this plugging.

DATE 4-3-91

Signed

James R. Kapp
(TECHNICIAN)

INV. NO. 31305