

1 020347

1-12 15-119-10171-0000² J

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- Drilled 3/10/59

SE NE NE, SEC. 26, T 33 S, R 29 N/E

4290 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9183

Lease Name C.L. Rexroad Well # 1

Operator: Bentley & Laing

County Meade 187.72

Name & Address P.O. Box 294

Well Total Depth 5776 feet

Wichita Falls, TX 76307

Conductor Pipe: Size feet

Surface Casing: Size 9 5/8 feet 1540

Abandoned Oil Well Gas Well X Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 3:30 p.m. Day: 9 Month: 1 Year: 19 91

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 5 1/2" at 5774', PBSD 5774', Perfs at 5676-5700'

1st plug pump 1 sx hulls and 25 sx cement at perforations, displace with mud,

2nd plug pump 50 sx cement at 1580',

3rd plug pump 50 sx cement at 700',

4th plug pump 15 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 2:30 p.m. Day: 12 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perforations,

displaced with mud, pressured up,

2nd plug pumped 50 sx cement at 1580',

3rd plug pumped 50 sx cement at 700',

4th plug pumped 15 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 2600' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Glenn Barlow (TECHNICIAN)

DATE 9-11-91

INV. NO. 30636

1-12