

To: 1 051894 2-3
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-21,362 - 0000
C NE NE SEC. 36 T 34 S, R 42 W
660 feet from NW section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Bennett B Well # 5

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

County Morton

Well Total Depth 5225 169.81 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1418

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Norseman Drilling, Inc. License Number 3779

Address 200 E. 1st, Ste. 307, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 2 Month: 2 Year: 1995

Plugging proposal received from Jim Barlow

(company name) Anadarko Petroleum Corp. (phone) 316-624-6253

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1450' with 50 sx cement, 2nd plug at 600' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2 a.m. Day: 3 Month: 2 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement,

2nd plug at 600' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED
(check) did not observe this plugging.

DATE 2-15-95

INV. NO. 42204

Signed Richard M. Lacey (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
FEB 07 1995
CONSERVATION DIVISION
WICHITA, KANSAS

FOR KCC-USE:

FORM C-1 7/91

EFFECTIVE DATE: 1-2-95

FORM MUST BE TYPED

DISTRICT # 1

State of Kansas

NOTICE OF INTENTION TO DRILL 129-21,362 - 0000 Alt

FORM MUST BE SIGNED

SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

BLANKS MUST BE FILLED

Expected Spud Date 1 month 5 day 95 year

Spot East ... NE... Sec 36. Twp 34. S, Rg 42. X West

OPERATOR: License # 4549 Name: ANADARKO PETROLEUM CORPORATION Address: P.O. BOX 351 City/State/Zip: LIBERAL, KANSAS 67905-0351 Contact Person: JIM BARLOW Phone: (316) 624-6253

660 feet from XXXXX / North line of Section 660 feet from East / XXXX line of Section IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 3779 Name: NORSEMAN DRILLING, INC.

County: MORTON

Lease Name: BENNETT "B" Well #: 5

Field Name: WILBURTON NW

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): UPPER MORROW "B"

Nearest lease or unit boundary: 660'

Ground Surface Elevation: 3478 (EST) feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 290'

Depth to bottom of usable water: 420' 440'

Surface Pipe by Alternative: X 1 2

Length of Surface Pipe Planned to be set: 1618'

Length of Conductor pipe required: NONE

Projected Total Depth: 5225'

Formation at Total Depth: CHESTER

Water Source for Drilling Operations: X well farm pond other

* Apply to DWR for Permit

Will Cores Be Taken? yes X no

If yes, proposed zone:

Table with columns: Well Drilled For, Well Class, Type Equipment. Rows include Oil, Gas, CWMO, Seismic, etc.

If CWMO: old well information as follows: Operator, Well Name, Comp. Date, Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depths: Bottom Hole Location

Exp. 6/28/95

AFFIDAVIT

460' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following...

Main form area with fields for Pusher (Jim Barlow), SPUD DATE (1-21-95), LENGTH SURFACE PLANNED (1418'), RESERVE PIT STATUS, RATHOLED AHEAD?, SURFACE PIPE (9 5/8" @ 1418' CONDUCTOR), ANHYDRITE T-B ELEVATION, TD (5225'), RAN PIPE @ DV TOOL, Arbuckle Plug, Hug./Council, Anhydrite Base @ 1450, 1/2 Base Anhyd. @ 600, 1/2 Plug @, Bottom Surface @, 40' Plug @, RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX, WATER WELL SX (Irr. Well Pond Hauling), TECHNICIAN S.S.C. DATE 2-2-95, TYPE OF CEMENT (60/40 6% grt), STARTING TIME (AM/PM) DATE, COMPLETE TIME (AM/PM) DATE 2-3-95, CEMENT COMPANY (Halliburton)

RECEIVED STATE CORPORATION COMMISSION FEB 07 1995