

15-129-10462-0000

① 060424

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Completed 3/20/57
C SW NW, SEC. 36, T 34 S, R 42 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5469
Operator: Anadarko Production Company
Name & Address: P. O. Box 351
Liberal, KS 67901

Lease Name Bennett Well # 1
County Morton 164.29
Well Total Depth 5055 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1484

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 10:00 am Day: 11 Month: January Year: 19 85

Plugging proposal received from Doug Blair
(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" set at 4693' PBTD 3850' Perfs at 3708-22 and 3774-96
Spot cement through 4 1/2" casing with heavy mud between plugs
1st plug pump 2 sx hulls and 25 sx cement to bottom
2nd plug at 2550' with 45 sx cement
3rd plug at 1550' with 40 sx cement
4th plug at 600' with 30 sx cement
5th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthie
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 pm Day: 11 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to bottom, 2nd plug
at 2550' with 45 sx cement, 3rd plug at 1550' with 40 sx cement, 4th plug at 600' with
30 sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 15 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2418' 4 1/2" casing. Used common cement by Sargent's.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE 1-18-85

Signed Paul A. Luthie
(TECHNICIAN)

INV. NO. 6579 FEB 18 1985
1-11