

To: 031469
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-129-10571-00-01

API NUMBER 15- Spud date 12/10/55
C SW, SEC. 35, T 34 S, R 42 W/EX
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corp.
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Watson Well # 1-35
County Morton 152.10
Well Total Depth 4680 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1506

Abandoned Oil Well _____ Gas Well _____ X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 8 a.m. Day: 20 Month: 10 Year: 19 97

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 4680' w/800 sx cement, CIBP 4465', Perfs at 2882-2992, 4527-36'
1st plug pump 25 sx cement and 3 sx hulls, displace to 2575'
2nd plug pump 25 sx cement at free point stub,
3rd plug pump 50 sx cement at bottom of surface, 4th plug pump 50 sx cement at 690',
5th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 12 p.m. Day: 23 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 35 sx cement at 2180-2080',
2nd plug pumped 50 sx cement at 1540-1390',
3rd plug pumped 50 sx cement at 690-590',
4th plug pumped 10 sx cement at 40'.
10-27-97

Remarks: Used common cement by Sargent & Horton. Recovered 2184' of 5 1/2" casing.
(Additional description is necessary, use BACK of this form.)

INVOICED

I (XXXXX / did not) observe this plugging.

DATE OCT 29 1997

Signed Steve Durrant (TECHNICIAN)

INV. NO. 49366