

To: 1 020411
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-415-129-10570-0000 135
API NUMBER 19- Drill Completion Date 5/6/57

NE SW, SEC. 35, T. 34 S, R. 42 W/E
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Taloga Mor "G" Well # 603
County Morton 147.64
Well Total Depth 4543 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1500

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 3 Month: 10 Year: 19 91

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4627' w/150 sx cement, PBD 4526', Perfs at 4516-26'
1st plug pump 1 sx hulls and 25 sx cement at perfs, displace plugs with heavy mud,
2nd plug at 2400' with 30 sx cement,
3rd plug at 1540' with 40 sx cement, 4th plug at 650' with 30 sx cement,
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:30 p.m. Day: 4 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs, displaced all plugs with heavy mud,

2nd plug pumped 30 sx cement at 2400',

3rd plug pumped 40 sx cement at 1540',

4th plug pumped 30 sx cement at 650',

5th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Sargent's. Recovered 2400' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-29-91
INV. NO. 33532

Signed Glenn R. Barlow (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
OCT 22 1991
CONSERVATION DIVISION
Wichita, Kansas