

9-915-129-10550-0000

1 031173

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15 - Drill Completion Date 12/5/58

C NE NW, SEC. 35, T 34 S, R 42 W/E
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Taloga Mor "G" Well # 304

Operator: Anadarko Petroleum Corporation

County Morton 150.31

Name & Address P.O. Box 351

Well Total Depth 4625 feet

Liberal, KS 67905-0351

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1433

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 11 a.m. Day: 6 Month: 9 Year: 19 91

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4624' w/175 sx cement, PBSD 4582', Perfs at 4529-41'

1st plug pump 1 sx hulls and 25 sx cement at perfs with tubing, load hole with mud,

2nd plug pump 40 sx cement at cut off if below 2000',

3rd plug pump 50 sx cement at 1480',

4th plug pump 40 sx cement at 700', 5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6 p.m. Day: 9 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls with 25 sx cement at 4500-4300',

2nd plug pumped 30 sx cement at 2400',

3rd plug pumped 40 sx cement at 1470',

4th plug pump 30 sx cement at 650-550',

5th plug pumped 10 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2410' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

WITNESSED BY M.A. MONDEN

INVOICED

(If applicable, observe this plugging.)

DATE 10-8-91

Signed Steve Shumant
(TECHNICIAN)

INV. NO. 33294

9-9