

9-23 15-129-10479-0000

1 020405

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- Drill Completion Date 11/7/58

C SE NE, SEC. 35, T. 34 S, R 42 W  
3300 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Taloga Mor "G" Well # 403  
County Morton 164.25  
Well Total Depth 5054 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1451

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 4:30 p.m. Day: 20 Month: 9 Year: 19 91

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4621' w/175 sx cement, PBTD 4687', Perfs at 4561-63'

1st plug pump 1 sx hulls and 20 sx cement at perfs, load hole with mud with tubing,

2nd plug pump 30 sx cement at 2020', displace with mud,

3rd plug pump 40 sx cement at 1500-1340',

4th plug pump 30 sx cement at 650-550', 5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5 p.m. Day: 23 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, loaded hole with mud with tubing,

2nd plug pumped 30 sx cement at 2020', displaced with mud,

3rd plug pumped 40 sx cement at 1500-1340',

4th plug pumped 30 sx cement at 650-550',

5th plug pumped 10 sx cement at 40 to -4'.

RECEIVED STATE CORPORATION COMMISSION

OCT 01 1991

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2024' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-8-91

INV. NO. 33297

9-23

Signed Glenn R. Barlow (TECHNICIAN)