

15-129-10549-0009-17

91 R

To: 1 020400
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 11/19/58

C SE NW, SEC. 35, T 34 S, R 42 W/X
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Taloga Mor "G" Well # 303

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351

County Morton 151.87

Liberal, KS 67905-0351

Well Total Depth 4673 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1425

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 8 a.m. Day: 13 Month: 9 Year: 19 91

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4630' w/300 sx cement, PRTD 4605', Perfs at 4504-10, 4520-23, 4526-48'
1st plug pump 1 sx hulls and 25 sx cement at perfs with tubing, load hole with mud,
2nd plug pump 30 sx cement at 2200-2100', 3rd plug pump 40 sx cement at 1470-1370',
4th plug pump 45 sx cement at 450-400', 5th plug pump 15 sx cement at 30' to -5'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 17 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement at perfs with tubing, load hole with mud,

2nd plug pumped 30 sx cement at 2200-2100,

3rd plug pumped 40 sx cement at 1470-1370',

4th plug pumped 45 sx cement at 450-400',

5th plug pumped 15 sx cement at 30' to -5'.

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2220' of 5 1/2" casing, 850' of 8 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 10-8-91

INV. NO. 33295

9-17

Signed Glenn R. Barlow (TECHNICIAN)