

1100247

TO: STATE CORPORATION COMMISSION

10-14

API NUMBER 15-175-21,738 - 0000
NW SE SW SW SEC. 8, T 33 S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 500 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 700 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HITCH "H" WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY SEWARD 211.25

OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 6500 FEET

OPERATOR: ANADARKO PETROLEUM CORP PRODUCTION CSG: SIZE 5 1/2 " FEET 4384

NAME AND PO BOX 351 SURFACE CASING: SIZE 8 3/8 " FEET 1677'

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR HALLIBURTON ENERGY SERVICES LICENSE NUMBER 5287

ADDRESS 1100 WEST PANCAKE, LIBERAL, KS 67901

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 14 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM JIM BARLOW

(COMPANY NAME) HALLIBIRTON ENERGY SERVICES (PHONE) 316-624-3879

WERE: PERFS AT 4237-4247

1ST PLUG MIX 25 SX CEMENT WITH 3 SX HULLS FROM 4247' TO 4027'. BACK OFF 5 1/2" CASING AT 2000' CIRCULATE HOLE. PULL CASING TO 1720'. 2ND PLUG SPOT 50 SX CEMENT AT 1720' PULL CASING TO 650'. 3RD PLUG SPOT 25 SX CEMENT AT 650'. PULL CASING TO 40'. 4TH PLUG CAP OFF WITH 10 SX CEMENT AT 40'-0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 14 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG MIX 25 SX CEMENT WITH 3 SX HULLS FROM 4247' TO 4027'. BACK OFF 5 1/2" CASING AT 2000'. CIRCULATE HOLE. PULL CASING TO 1720'. 2ND PLUG SPOT 50 SX CEMENT AT 1720' PULL CASING ATO 650'. 3RD PLUG SPOT 25 SX CEMENT AT 650'. PULL CASING TO 40'. 4TH PLUG CAP OFF WITH 10 SX CEMENT AT 40'-0'. 11-5-98

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. RECOVERED 2000' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

60270