

1100325

TO: STATE CORPORATION COMMISSION

API NUMBER NA 15-175-90230-0000 SEC. 8, T 33 S, R 34 W  
SW SW SW NE

00172-00-01

CONSERVATION DIVISION - PLUGGING SECTION 2840 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2542 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HITCH WELL # 1-8

TECHNICIAN'S PLUGGING REPORT 1/25/00 COUNTY SEWARD 89.05

OPERATOR LICENSE # 4549 WELL TOTAL DEPTH 2740 FEET

OPERATOR: ANADARKO PETROLEUM CORP PRODUCTION CSG: SIZE 7" @ 2595' WITH cmf. to surface

NAME AND PO BOX 351 SURFACE CASING: SIZE 10 1/2" @ 607' WITH NA SX

ADDRESS LIBERAL, KS 67905-0351

ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD WELL D-19,809 D/A       

OTHER WELL AS HEREINAFTER INDICATED       

PLUGGING CONTRACTOR BORDER-LINE, INC LICENSE NUMBER 7840

ADDRESS PO BOX 1043 ULYSSES, KS 67880-1043

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 25 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM       

(COMPANY NAME) BORDER-LINE, INC. (PHONE) 316-356-3381

WERE: PERFS AT 1220-1315

1ST PLUG SQUEEZE OF BOTTOM PERFS WITH 500# HULLS AND 50 SX CEMENT AT 1400 PSI. TOP OF CEMENT AT 1170'. PUMP 43 BBL OF 9# MUD DOWN 7" CASING. 2ND PLUG RUN IN TUBING TO 500' AND SPOT 40 SX CEMENT. 3RD PLUG SPOT 15 SX CEMENT CAP PLUG FROM 50' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART        NONE       

OPERATIONS COMPLETED: HOUR: 5:30 PM DAY: 25 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT       

1ST PLUG SQUEEZE OFF BOTTOM PERFS WITH 500# HULLS AND 50 SX CEMENT AT 1400 PSI. TOP OF CEMENT AT 1170'. PUMP 43 BBL OF 9# MUD DOWN 7" CASING. 2ND PLUG RUN IN TUBING TO 500' AND SPOT 40 SX CEMENT. 3RD PLUG SPOT 15 SX CEMENT CAP PLUG FROM 50' TO 0'.

RECEIVED  
STATE CORPORATION COMMISSION

FEB - 3 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED CONSERVATION DIVISION  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORMS)

I (DID) OBSERVE THIS PLUGGING

DATE 2/3/00 SIGNED Gary Winters

WV. NO. 061207

(TECHNICIAN) FORM CP-2/3