

1 060660

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,871-000R
C NE NE, SEC. 11, T 33 S, R 34 W/E
4620 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corp.
Name & Address: P. O. Box 351
Liberal, KS 67901

Lease Name McGee "A" Well # 1
County Seward 207.19
Well Total Depth 6375 St. Louis feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1625

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Gabbert-Hones, Inc. License Number 5842

Address 830 Sutton Place, Wichita, KS67202

Company to plug at: Hour: 10:00 pm Day: 2 Month: September Year: 19 85

Plugging proposal received from Jim Barlow

(company name) Anadarko (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1610' Elevation N/A

1st plug at 2600' with 50 sx cement

2nd plug at 1690' with 50 sx cement

3rd plug at 800' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:00 pm Day: 2 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2600' with 50 sx cmeent, 2ndplug at 1600' with 50 sx cement, 3rd plug at 800' with 50 sx cement, 4th & 5th plugs - solid bridge- hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement, 7thplug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE OCT 03 1985

SEP 27 1985

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 10303

CONSERVATION DIVISION Wichita, Kansas