

TS: 1 020820 11-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,684-0000
SW SW NW, SEC. 11, T 33 S, R 34 W/E
2970 feet from S section line
4950 feet from E section line
Lease Name Hitch Unit Well # 3-1
County Seward 208.00
Well Total Depth 6400 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1670

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67905-0351

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent and Horton Plugging, Inc. License Number 31151

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 8:30 a.m. Day: 14 Month: 11 Year: 19 94

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 5 1/2" at 6399' w/210 sx cement, PBD 6359', Perfs at 6184-6214'

1st plug pump 10,000 gal. Injectrol-G and 100 sx cement through cement retainer,

2nd plug pump 25 sx cement at 2800',

3rd plug pump 50 sx cement at 1700', 4th plug pump 40 sx cement at 700',

5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 p.m. Day: 16 Month: 11 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 10,000 gallons Injectrol-G and 100 sx cement through cement retainer,

2nd plug pumped 25 sx cement at 2800',

3rd plug pumped 50 sx cement at 1700',

4th plug pumped 40 sx cement at 700',

5th plug pumped 10 sx cement at 40 to -4'.

Remarks: Used Class H cement by Sargent & Horton. Recovered 2823' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

1 (If desired, observe this plugging.)

Signed Glenn R. Barlow (TECHNICIAN)

DATE 11-29-94

INV. NO. 11737