

To: 1020841 2-17  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,107-0000  
W/2 NE NE, SEC. 13, T. 33 S, R. 34 W/EX  
4620 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4476  
Operator: Whiting Petroleum Corporation  
Name & Address 1700 Broadway, Ste. 2300  
Denver, CO 80290

Lease Name Reimer Well # 1  
County Seward 143.49  
Well Total Depth 4415 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1593

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 8 a.m. Day: 16 Month: 2 Year: 1995

Plugging proposal received from Don Horton

(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

- were: 5 1/2" at 4414' w/125 sx cement, Perfs at 4206-10'  
1st plug pump 2 sx hulls and 25 sx cement at perfs,  
2nd plug pump 25 sx cement at 2412', displace with mud,  
3rd plug pump 45 sx cement at 1625',  
4th plug pump 35 sx cement at 650', 5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 17 Month: 2 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs,  
2nd plug pumped 25 sx cement at 2412', displaced with mud,  
3rd plug pumped 45 sx cement at 1625',  
4th plug pumped 35 sx cement at 650',  
5th plug pumped 10 sx cement at 40 to -4'.

All but top plug displaced with mud.

Remarks: Used common cement by Sargent & Horton. Recovered 2412' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(If desired, observe this plugging.)

**INVOICED**  
DATE 2-27-95  
INV. NO. 42284  
2-17

Signed Glenn R. Barlow  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
FEB 24 1995