

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20692-00-01
Spot: NWNW Sec/Twnshp/Rge: 14-33S-34W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: HITCH UNIT Well Number: 8-1
County: SEWARD Total Vertical Depth: 6340 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 6330 WITH 175 SX CMT
Surface Casing Size: 8.625 feet: 1588 WITH 800 SX CMT
206.05

Well Type: EOR UIC Docket No: E26115.8 Date/Time to Plug: 02/21/2003 10:05 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS WITH 25 SX CMT. 50 SX CMT AT 1600'. 40 SX CMT AT 600'. 10 SX CMT AT 40'.

Plugging Proposal Received By: JIM HOLLAND WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/21/2003 1:45 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 6245'. PERFS AT 6125-6227'. PUMP 400# HULLS & 25 SX CMT OVER PERFS. 1ST PLUG PULL TO 1600'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. 2ND PLUG PULL TO 600' & PUMP 40 SX CMT. 3RD PLUG PULL TO 40' & PUMP 10 SX CMT. STAYED FULL.

RECEIVED
FEB 28 2003
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2533' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED

DATE 2-28-03

INV. NO. 2003061252

Form CP-23