

To: 1 020737 1-28
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-21,316-0000
W/2 NE NE, SEC. 15, T. 33, S. R 34 W/2

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

660 feet from NS section line
1250 feet from E section line

Operator: Anadarko Petroleum Corporation
Name:
Address P.O. Box 351
Liberal, KS 67905-0351

Lease Name B & B Royalty A Well / 3
County Seward
Well Total Depth 6375 207.19 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1634

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2:30 p.m. Day: 21 Month: 1 Year: 1994

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

logs: 5 1/2" at 6030' w/235 sx cement, PBTD 5666', Perfs at 5650-58'

1st plug pump 1 sx hulls and 25 sx cement, displace with mud until pressures up,

2nd plug pump 40 sx cement at 2200', 3rd plug pump 50 sx cement at 1650',

4th plug pump 30 sx cement at 650', 5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 28 Month: 1 Year: 1994.

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement, displaced with mud, tagged at 5510'

2nd plug pumped 40 sx cement at 2200',

3rd plug pumped 50 sx cement at 1650',

4th plug pumped 30 sx cement at 650',

5th plug pumped 10 sx cement at 40 to -4'.

RECEIVED
STATE CORPORATION COMMISSION
FEB - 2 1994
CONSERVATION DIVISION
WICHITA, KANSAS

Used common cement by Sargent's. Recovered 2227' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

DATE FEB 02 1994 observe this plugging.

INV. NO. 39836

Signed Glenn R. Barlow
(TECHNICIAN)