

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- -191-20973-0000

C 5E NW, SEC. 29, T30S, R 30W

FEET FROM N/S SECTION LINE

FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5426

LEASE NAME Fullmer WELL # 1

OPERATOR: Dunne Gardner Pet. Inc
NAME & ADDRESS Ste. 250, 200W. Douglas
Wichita, Ks. 67202

COUNTY Sumner

WELL TOTAL DEPTH 4315 \$ 140.24 FEET

CONDUCTOR PIPE: SIZE 5 1/2" FEET 4310'

SURFACE CASING: SIZE 8 7/8" FEET 252'/250' 5x

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Kelso Csg. Pulling. LICENSE NUMBER 6050

ADDRESS Box 176, Chase, Ks. 67524 Rig. 550

COMPANY TO PLUG AT: HOUR: _____ DAY: 3 MONTH: 8 YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM DARRAL Kelso

(COMPANY NAME) Kelso Csg. Pulling. (PHONE) _____

WERE: drive bridge to bottom from 320', sand hole to 2900'
dump 5 sx. cement, shoot + pull 5 1/2" csq. spot 35 sx. cement
at 1100', spot cem. from 350' to sur.

PLUGGING PROPOSAL RECEIVED BY Don Thompson
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 12:15 P.M. DAY: 12 MONTH: 8 YEAR: 19 83

ACTUAL PLUGGING REPORT 8-3-83 United Cementing #4149 pumped water, finally
drove bridge to bottom. 8-4-83 SLM 3130, sand hole back to 2840' 8-5-83
lost wireline in hole, lost barler in hole. 8-8-83 Fished wireline. Left barler in hole
8-9-83 changed out rigs. 8-10-83 dumped sand on barler. dumped 10 sx
cemt. on barler. 8-11-83 shot + pulled 2032' 5 1/2", 8-12-83 Sun Cementing of Great Bend
spotted 35 sx cement. at 1086', spotted 100 sx cement. at 355' to sur.

REMARKS: Sun Cementing #13783

I (DID) / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Don Thompson
(TECHNICIAN)

INVOICED

DATE _____
INV. NO. 5308-W

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1983
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 6-83