

2 050851

4-19

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 191-21,288 - 0000

NW NW SE, SEC. 29, T 30 S, R 3 WX

TECHNICIAN'S PLUGGING REPORT

*Unsubscribed*  
*Chesnut*

Operator License # 5719

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

Operator: SLMW Energy Company

Lease Name Hemberger Well # 2

Name & Address 4818 S. Knoxville

County Sumner 139.82

Tulsa, OK 74135

Well Total Depth 4302 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8-5/8 feet 200

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gressel Corporation License Number 5822

Address P. O. Box 322, Haysville, KS 67060

Company to plug at: Hour: 8:00 Day: 18 Month: 4 Year: 19 89

Plugging proposal received from \_\_\_\_\_

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: 5-1/2" set @ 4298' w/125 sx cement & perf @ 4295' to 4298' - sand back  
to 4250' & pump 5 sx cement - shoot & pull casing - .35 sx above & below salt  
& from 250' to surface

Plugging Proposal Received by John Sanders  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00a Day: 19 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT Sanded back to 4250' & dumped 5 sx cement w/dump bailer -  
shot & pulled 2617' of 5-1/2" casing - squeezed 8-5/8" with 35 sx cement then  
8 sx gel, then 35 sx cement, then 8 sx gel, then 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

APR 24 1989

Remarks: United #4824 40/60 poz CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-27-89

WEL. NO. 24510

*WJ*

Signed Glenn L. Ward  
(TECHNICIAN)