

10-4 RECEIVED  
KANSAS CORPORATION COMMISSION

2-050287

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 207B  
Wichita, Kansas 67202

CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-191-21,145-0000

C NE NE, SECTION 29 TOWNSHIP 30 RANGE 3W

OPERATOR LICENSE # 30742 4620 FEET FROM S SECTION LINE  
660 FEET FROM E SECTION LINE

OPERATOR PALOMINO PETROLEUM INC  
NAME & 4924 SE 84TH STREET  
ADDRESS NEWTON KS 67114-8827

LEASE NAME: HARTMAN #3 139.62  
COUNTY: SUMNER  
WELL TOTAL DEPTH: 4296'

PIPE: 5-1/2" @ 4288'

SURFACE CASING: 8-5/8" @ 280'

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: VAL ENERGY INC  
ADDRESS: PO BOX 322 HAYSVILLE KS 67060-0322 LICENSE: 5822

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 4 MONTH: 10 YR: 1994

PLUGGING PROPOSAL RECEIVED FROM: DIST 2  
COMPANY NAME: ALLIED CEMENTING PHONE: 913-483-2627

WERE: SAND BACK & SPOT 5 SX CMT @ 4230' - SHOOT 5-1/2" CSG @ 2267' - PULL CSG TO 770' & SPOT 35 SX CMT - PULL CSG TO 335' & CIRC TO SURF - PULL CSG OUT OF HOLE AND TOP OFF W/CMT

PLUGGING PROPOSAL RECEIVED BY: TODD ALLAM

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (        ) PART ( X ) NONE (        )

COMPLETED: HOUR: 10:30 DAY: 4 MONTH: 10 YEAR: 1994

ACTUAL PLUGGING REPORT:  
SANDED BACK & SPOTTED 5 SX CMT @ 4230' - SHOT 5-1/2" CSG @ 2267' - PULLED CSG TO 720' & SPOTTED 35 SX CMT - PULLED CSG TO 335' & CIRC CMT TO SURF - PULLED CSG OUT OF HOLE & TOPPED OFF W/CMT


REMARKS: ALLIED #0763 220 SX CMT 60/40 POZ 4% GEL

I DID OBSERVE THIS PLUGGING.

**INVOICED**

DATE 10-26-94

INV. NO. 41520

  
Jerry Slapak

(AGENT)

FORM CP-2/3  
REV. 3/90