

2040506

9-20

- 0000 49

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 191-21,415 D-21,019

NW SW, SEC. 29, T 30 S, R 3 WXB

1650 feet from S section line

4290 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 3909

Lease Name Friess Well # A-2

Operator: Pluggers, Inc.

County Sumner 145.54

Name &amp; Address P. O. Box 782050

Well Total Depth 4478 feet

Wichita, KS 67278

Conductor Pipe: Size feet

316-636-4390

Surface Casing: Size 8-5/8 feet 257

Abandoned Oil Well Gas Well Input Well SWD Well X D&amp;A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number 6050

Address Chase, KS

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Mark McCabe

(company name) Kelso Casing (phone)

were: Sand to 4080' &amp; 5 sx - 4-1/2 4477' - PBTD 4580' - Perf 4130' - 4210'

50' plug at 950' - 50' plug @ 600'

STATE CORPORATION COMMISSION

SEP 26 1989

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None ✓

Operations Completed: Hour: 16:00 Day: 20 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT The perforations were sanded back to 4080' &amp; capped with 5 sx

cement - 4-1/2" was shot loose from 3100' - 4-1/2" casing was pulled to 930'

where a 50' plug was spotted in place - the 4-1/2" casing was then pulled to 600'

where another 50' plug was spotted - 4-1/2" casing was pulled to 312' and the well

was cemented to surface.

Remarks: Sun Cementing - Eureka, KS #2629 60/40 4% gel

(if additional description is necessary, use BACK of this form.)

INVOICED

(if additional description is necessary, use BACK of this form.)

DATE 9-25-89

Signed (TECHNICIAN)

INV. NO. 25979