

2040281

API NUMBER 15-095-21185-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW/NE/NW, SEC. 4, T 30 S, R 6 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4950 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5457
Operator: BHP (Americas)
Name & Address: Petroleum Corp. Inc.
Rt Box 4 3030 NW Expressway
Spivey KS. 67142
Oklahoma City, OK 73112

Lease Name Ravenstein Well # 1
County Kingman 143.65
Well Total Depth 4920 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 237'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____
Other well as hereinafter indicated _____

RECEIVED
D&A
CONSERVATION
COM. DIV. WICHITA, KS

Plugging Contractor Hayes Well Service License Number 7-29-86
Address Attaica KS.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Paul Harryman
(company name) BHP (phone) _____

were: 5 1/2 4416, PBTD 4370 Perfs 4089-91 CIBP 3650
CIBP 4015 Perf. 3526-32
Perf 3706-10 CIBP 3460
CIBP 3695 Perf 3244-48
Perf 3670-72 CIBP 3190

Rec 2050 Plugging Proposal Received by Dist office #2
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1230 Day: 22 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT Great Guns Wire line Service ran a
CIBP in the hole to 3190'. The 5 1/2 casing was shot off and
recovered from 2050'. The top was squeeze plugged thru
the 8 5/8" surface by pumping 2 sks of hulla, 15 sks of gel, 1 sk
of hulla and 65 sks of Howco-Lite thru a sledge.

Remarks: HOWCO 436592 mx 650# SI 350#
(Additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 29 1986

INV. NO. 14540

Signed Steve Deini
(TECHNICIAN)