

2050191

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-09.5-21,487-0000

NW/NE SEC. 8, T. 30 S, R. 6 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name messenger Well # H-#1

Operator Name & Address Pickwell Drly. Co.

County Kingman 145.02

110 N. Market St. 205

Well Total Depth 4462 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corp License Number _____

Address Medicine Lodge, Ks.

Company to plug at: Hour: 9:AM Day: 5 Month: NOV Year: 19 84

Plugging proposal received from Don Aumiller

(company name) Pickwell Drly. Co. (phone) _____

were: P.B. T.D. 4139 Perf. @ 4061-63 sand back & dump

4 5/8" cement shot & pull pipe,

pump 125 ex. cement for top plug.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

11-16-84

Plugging Proposal Received by Glen J. Ward
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:PM Day: 5 Month: NOV Year: 19 84

ACTUAL PLUGGING REPORT sand back to 4000 ft. & dump 4 ex.

cement. shot & pulled 3580 ft. of 4 1/2 casing.

Pumped 10 ex. gel & 5 ex. balls then 125 ex cement,

cement fell 60 ft. waited 1 hr. & topped of with

20 ex. cement to top.

Remarks: Allied Cementing ticket # 39063
(If additional description is necessary, use BACK of this form.)

(I did) / (did not) observe this plugging.

DATE 11-27-84

Signed Glen J. Ward
(TECHNICIAN)

INV. NO. 4898

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-095-21,487 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

EASE OPERATOR Pickrell Drilling Company OPERATORS LICENSE NO. 5123

ADDRESS 110 N. Market, Suite 205, Wichita, KS 67202 PHONE # (316) 262-8427

EASE (FARM) Messenger 'H' WELL NO. 1 WELL LOCATION NW NW SE COUNTY Kingman

SEC. 8 TWP. 30S RGE. 6 (E) (W) TOTAL DEPTH 4462 (RTD) PLUG BACK TD 4139

Check One:

OIL WELL _____ GAS WELL X Attempted completion D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 218' CEMENTED WITH 165 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT 4061'-4063'

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Dump sand and plug off bottom. Dump

cement on top of sand w/dump bailer. Shoot off pipe and POOH. Set wood plug at 250'.

Plug to surface w/cement.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not, explain) In process of filing ACO-1 form.

DATE AND HOUR PLUGGING IS TO BEGIN 10-31-84

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: Mr. Don Aumiller 10/29/84

PHONE # (316) 532-3579

ADDRESS 1340 North Spruce, Kingman, Kansas 67068

PLUGGING CONTRACTOR Clark Corporation LICENSE NO. 583

ADDRESS 107 W. Fowler, Box 187, Medicine Lodge, KS 67104 PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack Gurley
(Operator or Agent)

DATE: October 26, 1984