

6-30-87

API NUMBER 15- 175-20,452 - 0000

To: 1 050918
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE NE, SEC. 27, T 32 S, R 33 W/E
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Lease Name B.H. Lemert "B" Well # 1

Operator: Amoco Production Company
Name & Address P.O. Box 432
Liberal, KS 67901

County Seward 195.⁰⁰
Well Total Depth 6000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1586

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS 67877

Company to plug at: Hour: 10 a.m. Day: 30 Month: 6 Year: 19 87

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 6000' PBD 4686' Perfs at 4782-87, 4898-4900, 5870-83'

1st plug set CIBP at 4686',

2nd plug pump 50 sx cement at 2600', 3rd plug pump 50 sx cement at 1550',

4th plug pump 35 sx cement at 800', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 30 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug CIBP at 4686',

2nd plug pumped 50 sx cement at 2600',

3rd plug pumped 50 sx cement at 1550',

4th plug pumped 35 sx cement at 800',

5th plug pumped 10 sx cement at 40'.

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 1987
7-2-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. Recovered 2620' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

Signed Richard M. Lacey (TECHNICIAN)

DATE 7-2-87

INV. NO. 17419