

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

10-6

API NUMBER: 15-191-20,262-0000  
SE, SE, SW, SECTION 21 TOWNSHIP 30 RANGE 03W

OPERATOR LICENSE # 5822 610 FEET FROM S SECTION LINE  
3250 FEET FROM E SECTION LINE

OPERATOR VAL ENERGY, INC.  
NAME & P.O. BOX 322  
ADDRESS HAYSVILLE, KS 67060

LEASE NAME: SPEXARTH #1  
COUNTY: SU  
WELL TOTAL DEPTH: 4345 PB 4275'  
PIPE: 4 1/2" @ 4340'

141.21

SURFACE CASING: 8 5/8" @ 253'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: VAL ENERGY, INC.  
ADDRESS: P.O. BOX 322, HAYSVILLE, KS 67060 LICENSE: 5822

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 6 MONTH: 10 YR: 1995


PLUGGING PROPOSAL RECEIVED FROM: DISTRICT #2  
COMPANY NAME: ALLIED CEMENTING PHONE: 316-886-5926  
WERE: SAND BACK AND SPOT 5 XS. CMT. @ 2920'. SHOT 4 1/2"  
CASING @ 2640' AND PULL UP TO 700'. SPOT 35 XS. CMT. @  
700'. PULL CASING UP TO 300' AND CIRCULATE CMT. TO  
SURFACE. PULL CASING OUT OF HOLE AND TOP OFF WITH CMT.

PLUGGING PROPOSAL RECEIVED BY: TODD ALLAN  
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 11:00 DAY: 6 MONTH: 10 YEAR: 1995  
ACTUAL PLUGGING REPORT:

SANDED BACK AND SPOTTED 5 XS. CMT. @ 2920'. SHOT 4  
1/2" CASING @ 2640' AND PULLED UP TO 700'. SPOTTED 35  
XS. CMT. @ 700'. PULLED CASING UP TO 300' AND CIR-  
CULATED CMT. TO SURFACE. PULLED CASING OUT OF HOLE AND  
TOPPED OFF WITH CMT.

REMARKS: ALLIED #2069. 150 XS. CMT 60/40 POZ. 2% GEL.  
I DID OBSERVE THIS PLUGGING.

  
\_\_\_\_\_  
Jerry Clark (AGENT)

FORM CP-2/3  
REV. 3/90

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 18 1995

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 10-26-95

INV. NO. 43864

Doc