

4-17

250
RECEIVED
STATE CORPORATION COMMISSION
MAY 1 1990
Conservation Division
Wichita, Kansas

2-050956

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-191-20,264-0000

150' S/C NE SW, SECTION 21 TOWNSHIP 30 RANGE 3W

OPERATOR LICENSE # 4569 1500 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR 4569
NAME & Jay Boy
ADDRESS 224 E. Douglas - S. 425
Wichita, KS 67202

LEASE NAME: Spexarth #2
COUNTY: Sumner
WELL TOTAL DEPTH: 4330
CONDUCTOR PIPE: inch @ feet
SURFACE CASING: 8-5/8 inch @ 249 feet

140.73

ABANDONED OIL WELL GAS WELL INPUT WELL SHD D&A
OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Rockhold Engineering
LICENSE: 5111

ADDRESS:

COMPANY TO PLUG AT: HOUR: DAY: 13 MONTH: 4 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM:
COMPANY NAME: PHONE:

WERE: 4-1/2" set @ 4330' & perf @ 3831-35' - sand back to 3800' & 4 sx cmt - shoot & pull pipe - spot 30 sx cmt @ 1000' & 700' & from 300' to surface.

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1:00p DAY: 17 MONTH: 4 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded back to 3800' & dumped 4 sx cmt w/dump bailer - shot 4-1/2" @ 2662 and pulled to 1000' & spotted 30 sx cmt - pulled 10 joints & spotted 30 sx @ 700' - pulled 2 joints & circ from 300' to surface.

REMARKS: Howco #881775 40/60 poz

I DID OBSERVE THIS PLUGGING.

INVOICED

Glenn Ward
Glenn Ward (AGENT)

DATE 5-7-90
INV. NO. 28044 28069

FORM CP-2/3
REV. 3/90

nk