

2 040534

4-21

50
R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 191-20,266-0000

C SE SW, SEC. 21, T 30 S, R 3W W/E

660 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4569

Lease Name Good Well # 1

Operator: Jay Boy Oil Company

County Sumner 140.24

Name & Address 224 East Douglas, #425

Well Total Depth 4315 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8-5/8 feet 248

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111

Address Great Bend, KS

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Rick Davis

(company name) Rockhold Engineering (phone) _____

were: 5-1/2" 4282' perfs 3212' - 20'

PBTD 4230'

Sand to 3160' & 5 sx - 35 sx at 1000' - 35 sx at 700' - circ cmt 300' to 0'.

Plugging Proposal Received by Steve Van Gieson (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 17:00 Day: 21 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT A bridge was found in the 5-1/2" at 1230' - Halliburton was called to pump bridge down the hole - after pumping on 5-1/2" discovered that 5-1/2" was collapsed at 1250' and not bridged as first thought - sand was dumped down 5-1/2" to 1200' & capped with 5 sx - 5-1/2" was shot loose at 1125' & pulled to 1000' for the first cmt plug of 35 sx. The pipe was pulled to 700' where another 35 sx was spotted - 5-1/2" was then pulled to 300' and cmt was circ to surf.

Remarks: Howco #881871 150 sx 60/40 poz (If additional description is necessary, use BACK of this form.)

INVOICED (If you will observe this plugging.)

DATE 5-22-90

Signed [Signature] (TECHNICIAN)

INVOICE NO. 28192