

5-7

2-040549

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 191-20,279-0000

SW NE, SECTION 21 TOWNSHIP 30 RANGE 3W

OPERATOR LICENSE # 4569 3150 FEET FROM S SECTION LINE
2130 FEET FROM E SECTION LINE

OPERATOR Jay Boy Oil Company
NAME & ADDRESS 224 E. Douglas, #425
Wichita, KS 67202

LEASE NAME: Cecil #1
COUNTY: Sumner
WELL TOTAL DEPTH: 4314' - 140.21
CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 234'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Rockhold Engineering

ADDRESS: Great Bend, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Rick Davis

COMPANY NAME: Rockhold Engineering PHONE: _____

WERE: 4-1/2" @ 4312' - perms 4350' - sand to 4300' & 4 sx -
35 sx @ 1000' - 35 sx @ 700' - circ 300' to 0

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 16:30 DAY: 7 MONTH: 5 YEAR: 1990

ACTUAL PLUGGING REPORT:

Sand dumped inside 4-1/2" to 4300' & capped w/4 sx
cmt - casing shot loose at 2715' & pulled to 1000' & 35
sx cmt spotted - casing pulled to 700' & 35 sx cmt
spotted - casing pulled to 300' & cmt circ to surf.

REMARKS: Howco 60/40 poz

I DID OBSERVE THIS PLUGGING.

RECEIVED
STATE CORPORATION COMMISSION

Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90

INVOICE AUG 15 1990

DATE: 8-17-90 CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 28999

[Handwritten mark]