

1 020266

11-20

API NUMBER 15-189-21,223 A-0001

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

N/2 NE SE, SEC. 15, T 31 S, R 35 W/E

2130 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30090

Lease Name Churchman Bible Well # 4

Operator: J & J Energies, Inc.

County Stevens 15275

Name & Address 2609 South Ong 1605 S. Orchard

Well Total Depth 4700 feet

Amarillo, TX 79109

Conductor Pipe: Size \_\_\_\_\_ feet

OTTAWA, KS 66067

Surface Casing: Size 8 5/8 feet 1830

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2:30 p.m. Day: 17 Month: 11 Year: 19 89

Plugging proposal received from Don Horton

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 4700' PBD 4660' Perfs at 4610 & 4500' Stage tool at 2700'-not opened

TOC 3000'

1st plug pump 1 sx hulls and 20 sx cement at perforations, 4400-4610', load hole with heavy

mud, 2nd plug pump 25 sx cement at 2600', 3rd plug pump 35 sx cement at 1880-1780',

4th plug pump 35 sx cement at 700', 5th plug pump 10 sx cement at 40' to 3' below GL.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 20 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perforations,

4400-4610', loaded hole with heavy mud,

2nd plug pumped 25 sx cement at 2600',

3rd plug pumped 35 sx cement at 1880-1780',

4th plug pumped 35 sx cement at 700',

5th plug pumped 10 sx cement at 40' to 3' below GL.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 27 1989

11-27-89  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2714' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(copy to XXXXXX) observe this plugging.

DATE 12-6-89

Signed Glenn R. Barlow  
(TECHNICIAN)

INV. NO. 26642

11-20