

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

15-175-20236-0000

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-175-20236 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Questa Energy Corporation KCC LICENSE # 03062 <sup>7/98</sup>  
(owner/company name) (operator's)

ADDRESS P.O. Box 19297 CITY Amarillo

STATE Texas ZIP CODE 79114 CONTACT PHONE # (800) 358-8161

LEASE Lemert WELL# 2 SEC. 22 T. 32S R. 33 (East/West)

NE-NE SPOT LOCATION/0000 COUNTY Seward

2310 FEET (in exact footage) FROM (S/N) LINE OF SECTION (NOT Lease Line)

2135 FEET (in exact footage) FROM (E/W) LINE OF SECTION (NOT Lease Line)

Check one: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8 5/8 SET AT 1584' CEMENTED WITH 650 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 5875' CEMENTED WITH 325 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs 5683-86', CIBP 5260', perfs 4884-94'

ELEVATION 2767' T.D. 5900' PBDT 5842' ANHYDRITE DEPTH 1593' (base)  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING 20 sxs plug from 4994-4756 Cut off 4 1/2 csg approx 2600'

50 sxs plug 1593-1436', 40 sxs plug 800-680', 50 sxs plug from 400-250'. 10 sxs plug

from 40-10', Cut off 8 5/8 csg 4' below ground level and cap. \*

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED?

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Rob McGarraugh PHONE# 806 435-4622

ADDRESS P.O. Box 578 City/State Perryton, Tx

PLUGGING CONTRACTOR Sargents Casing Pulling Service KCC LICENSE # 6547 <sup>6/98</sup>  
(company name) (contractor's)

ADDRESS P.O. Box 506 Liberal, KS 67905-0506 PHONE # (310) 624-7455

PROPOSED DATE AND HOUR OF PLUGGING (if known?) \_\_\_\_\_

PAYMENT OF THE PLUGGING FEE (K.S.A. 52-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-19-98 AUTHORIZED OPERATOR/AGENT: Rob McGarraugh RECEIVED

(signature)

FEB 23 1000  
2-23-98  
Wichita, Kansas

Note: Displace all plugs with drilling mud, Class H cement  
@ 16.4#/gal 1.06 CU FT/sx yield.

RECEIVED  
STATE OF KANSAS

FEB 23 1969

CONSERVATION DIVISION  
Wichita, Kansas



# GAMMA-GUARD LOG

COMPANY YUCCA PETROLEUM COMPANY WELL LEMERT # 2-22 FIELD LEMERT County SEWARD State KANSAS	COMPANY <u>YUCCA PETROLEUM COMPANY</u> <u>15-175-20236</u>
	WELL <u>LEMERT # 2-22</u>
	FIELD <u>LEMERT</u>
	COUNTY <u>SEWARD</u> STATE <u>KANSAS</u>
Location: <u>2310' fr S/L</u> <u>2135' fr E/L</u>	Other Services: <u>CA/V</u>
Sec. <u>22</u> Twp <u>32S</u> Rge <u>33W</u>	

Permanent Datum <u>GROUND LEVEL</u> Elev. <u>2757'</u> Log Measured From <u>KELLY BUSHING, 10</u> Ft. Above Perm. Datum Drilling Measured From <u>KELLY BUSHING</u>	Elev.: <u>K.B. 2767'</u> <u>D.F. ---</u> <u>G.L. 2757'</u>
---	--

Date	8-27-74			
Run No.	ONE			
Depth-Driller	5900'			
Depth-Welex	5895'			
Btm. Log Inter.	5890'			
Top Log Inter.	1550'			
Casing-Driller	8-5/8" @ 1580'	@	@	@
Casing-Welex	1584'			
Bit Size	7-5/8"			
Type Fluid in Hole	W. B. MUD CHEMICALS			
Dens.   Visc.	9.1   143			
pH   Fluid Loss	7.4   11.2ml	ml	ml	ml
Source of Sample	FLOW LINE			
R <sub>100</sub> @ Meas. Temp.	0.33 @ 80°F	@ °F	@ °F	@ °F
R <sub>100</sub> @ Meas. Temp.	0.24 @ 78°F	@ °F	@ °F	@ °F
R <sub>100</sub> @ Meas. Temp.	0.47 @ 78°F	@ °F	@ °F	@ °F
Source R <sub>100</sub> R <sub>100</sub>	MEAS.   MEAS.			
R <sub>100</sub> @ BHT	0.22 @ 126°F	@ °F	@ °F	@ °F
Time Since Circ.	4 HRS.			
Max. Rec. Temp.	126°F @ 5850'	°F @	°F @	°F @
Equip.   Location	8479   LIB.			
Recorded By	REEVES			
Witnessed By	MR. VAUGHN			

RECEIVED  
STATE COMMISSION

FEB 23 1988

CONSERVATION DIVISION  
Wichita, Kansas



## Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Susan M. Seltam, Commissioner Cynthia L. Claus, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

February 25, 1998

Questa Energy Corporation  
P O Box 19297  
Amarillo TX 79114

Lemert #2  
API 15-175-20,236  
2310 FSL 2135 FEL  
Sec. 22-32S-33W  
Seward County

Dear Rob McGarraugh,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760