

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-21185-00-00
Spot: W2NESWSW Sec/Twnshp/Rge: 16-31S-35W
990 feet from S Section Line, 4292 feet from E Section Line
Lease/Unit Name: HE SHULER Well Number: 2
County: STEVENS Total Vertical Depth: 6250 feet

Operator License No.: 33002 Conductor Pipe: Size feet: 203.13
Op Name: WESTPORT OIL AND GAS COMPANY LP Surface Casing: Size 8.625 feet: 1766 WITH 780 SX CMT
Address: 5735 PINELAND, SUITE 300 Production: Size 5.5 feet: 6250 WITH 840 SX CMT
DALLAS, TX 75231 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/11/2002 10:00 AM

Plug Co. License No.: 8733 Plug Co. Name: DUNKIN, JERRY, INC.

Proposal Rcvd. from: BUTCH DUNCAN Company: DUNKIN, JERRY, INC. Phone: (580) 237-6152

Proposed Plugging Method: CIBP @ 5900' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1800' WITH 20 SX CMT. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 09/11/2002 11:45 AM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 6225'. PERFS AT 5966-94'. CMT TOP @ 1320'. CIBP @ 5900' WITH 2 SX CMT. PULL CASING OUT OF HOLE. 1ST PLUG RAN TUBING TO 1230' AND SPOT 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. STAYED FULL.

RECEIVED

SEP 16 2002

KCC WICHITA

Remarks: USED CLASS A CEMENT BY JERRY DUNKIN, INC. RECOVERED 1223' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed

(TECHNICIAN)

SEP 12 2002

9-18-02

2003060513

Form CP 2/3