

1 090048

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-189-21,036 - 0000

SE NW NW, SEC. 17, T 31 S, R 35 W/E

4290 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Lease Name J.F. Phillips Well # 4

Operator: Mobil Oil Corporation

County Stevens 90.35

Name & Address P.O. Box 5444

Well Total Depth 2780 feet

Denver, CO 80217

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 632

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address Box F, Sublette, KS

Company to plug at: Hour: 11 a.m. Day: 13 Month: 2 Year: 19 90

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 2779' PBD 2754' Perfs at 2574-2736' Elevation 2992' GL

1st plug pump 3 sx hulls and 30 sx cement,

2nd plug pump 25 sx cement at 1900',

3rd plug pump 25 sx cement at 700',

4th plug pump 5 sx cement at 40'.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 13 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. cotton seed hulls, 30 sx cement,

10 barrels gel, 25 sx cement, 25 barrels gel, 25 sx cement, 12 barrels gel, and 5 sx

cement. Last plug (5 sx cement) will be added after cutting off casing 5' below

ground level.

5 1/2" at 2779' with 445 sx cement circulated to surface.

Remarks: Used common cement by Midwest Casing Pulling. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICE
DATE 2-16-90
NO. 27488
2-13

STATE CORPORATION COMMISSION
OBSERVE THIS PLUGGING
FEB 15 1990
CONSERVATION DIVISION
Wichita, Kansas

Signed Michael Wilson
(TECHNICIAN)