

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-25
API NUMBER 15-189-20,758-0000
C NW, SEC. 18, T 31 S, R 35 WAEX
3960 feet from S section line
3960 feet from E section line
Lease Name Hinshaw Estate Well # 3
County Stevens 101.56
Well Total Depth 3125 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 814

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208

Operator: Mobil Oil Corporation
Name &
Address P.O. Box 5444
Denver, CO 80217

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P.O. Box F, Sublette, KS 67877

Company to plug at: Hour: 10 a.m. Day: 25 Month: 4 Year: 19 89

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 3125' PBD 3083' Perfs at 2910-38'

1st plug pump down 5 1/2" casing with 2 sx hulls and 25 sx cement, gel spacer to anhydrite,

2nd plug pump 25 sx cement at 1500',

3rd plug pump 25 sx cement at 750',

4th plug pump 5 sx cement at 40'. (Have 100 sx cement for backside if needed.)

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4 p.m. Day: 25 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls, 25 sx cement, 4 sx gel, 25 sx cement,

3 sx gel, 25 sx gel, 3 sx gel, 5 sx cement,

2nd plug pumped 4 sx cement down 8 5/8" X 5 1/2" annulus.

(5 1/2" circulated)

RECEIVED
STATE CORPORATION COMMISSION

MAY - 1 1989
5-1-89

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. No casing recovery.

(If additional description is necessary, use BACK of this form.)

~~XXXX~~ did not observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE 5-8-89

INV. NO. 24639