

231-R

1 125017

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 189-20,615 - 0000
C NW , SEC. 18 , T 31 S, R 35
3960 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208
Operator: Mobil Oil Corporation
Name & Address: 123 East 11th Street
Liberal, KS 67901

Lease Name Hinshaw Estate Well # 2
County Stevens 99.55
Well Total Depth 3063 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 723

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 1:30 pm Day: 21 Month: April Year: 19 86

Plugging proposal received from Ed Eves

(company name) Midwest (phone) 316-356-2113

were: 5 1/2" at 3043' (circulated) PBD 3043' Perfs at 2872-2966

1st plug pump 5 1/2 bbls mud and 6 sx cement and 36 1/2 bbls mud and 7 sx cement

2nd plug pump 5 1/2 bbls mud 6 sx cement, 6 bbls mud and 12 sx cement and 15 bbls mud and 6 1/2 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 pm Day: 21 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 5 1/2 bbls mud and 6 sx cement to 2820', 2nd plug spotted 36.5 bbls mud to 1340, 7 sx cement to 1290, 5.5 bbls mud to 1065, 6 sx cement to 1015, 6 bbls mud to 773, 12 sx cement to 673. Spotted 5 bbls gel, 13 sx cement. Pressure 350#

RECEIVED STATE CORPORATION COMMISSION

APR 29 1986

Remarks: No recovery. Used Class A cement by Midwest. (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

observe this plugging.

Signed *Lew P. Parker* (TECHNICIAN)

MAY 05 1986

DATE _____

INV. NO. 4-21