

To: 1 22668  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

15-189-10025-0000  
API NUMBER 15- Drilled 1962  
SW NE, SEC. 21, T. 31 S, R. 35 W/E  
3300 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5208  
Operator: Mobil Oil Corporation  
Name & Address: 2319 N. Kansas  
Liberal, KS 67901

Lease Name Leffler-Gaskill Well # 3  
County Stevens  
Well Total Depth 6338 205,98 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 614

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 11:30 a.m. Day: 30 Month: 4 Year: 19 93

Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

were: 6 5/8" at 3443' w/350 sx cement, PBTD 2789', Perfs at 3273-79', 6278-87'  
1st plug cement plug at 3331-2789', 2nd plug CIBP at 3334-3331',  
Load-hole with mud, 3rd plug run tubing to 1730' and pump 30 sx cement,  
4th plug pump 44 sx cement at 650',  
5th plug pump 6 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn R. Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour 5 p.m. Day: 30 Month: \_\_\_\_\_ Year: 19 93

ACTUAL PLUGGING REPORT 1st plug cement plug at 3331-2789',  
2nd plug CIBP at 3334-3331', Hole loaded with mud:  
3rd plug ran tubing to 1730' and pumped 30 sx cement,  
4th plug pumped 44 sx cement at 650',  
5th plug pumped 6 sx cement at 40 to -4'.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 10 1993  
DIVISION

Remarks: Used common cement by Sargent & Horton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Glenn R. Barlow  
(TECHNICIAN)

5-14-93  
37710  
4-30