

To: 1 020663
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200, COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,310-0000 97 R
C SW NE, SEC. 15, T. 32 S, R. 33 W/E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3871
Operator: Hugoton Energy Corporation
Name & Address 229 E. William, Ste. 500
Wichita, KS 67202

Lease Name Edna Scott Well # 2
County Seward 196.95
Well Total Depth 6060 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1620

Abandoned Oil Well Gas Well _____ Input Well _____ SMD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 16 Month: 4 Year: 19 93
Plugging proposal received from Manny Boatright
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 5150' w/300 sx cement, PBTD 5150', Perfs at 4967-69'
1st plug pump 55 sx cement at perfs with celoflake, displace to 4770'
2nd plug pump 80 sx cement at 2900', 3rd plug pump 50 sx cement at 1650',
4th plug pump 40 sx cement at 700',
5th plug pump 10 sx cement at 40 to -4'. Mud between all plugs.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 6 p.m. Day: 21 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 55 sx cement with celoflake at perfs, displaced
to 4770' on 4/16/93.

4/21/93 2nd plug pumped 80 sx cement at 2900',
3rd plug pumped 50 sx cement at 1650',
4th plug pumped 40 sx cement at 700',
5th plug pumped 10 sx cement at 40 to -4'. Mud between all plugs.

Remarks: Used 60/40 Pozmix 6% gel by D & S. Recovered 3200' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.) APR 30 1993

I (did / ~~did not~~) observe this plugging.
5-11-93
37664

Signed Glenn R. Barlow
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION