

To: 1 051232
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,230 -0000
SE SE, SEC. 15, T 32 S, R 33 W/R
660 feet from S section line
660 feet from E section line
1) Edna Scott #1
Lease Name 2) Scott GU B Well # 1
(Dual completion with two names)
County Seward 198.54

TECHNICIAN'S PLUGGING REPORT
Operator License # 5952
Operator: Amoco Production Company
Name & Address P.O. Box 800, Rm. 1846
Denver, CO 80201

Well Total Depth 6109 feet
Conductor Pipe: Size feet
Surface Casing: Size 9 5/8 feet 1890

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Midwest Casing Pulling License Number 6497
Address Box F, Sublette, KS 67877

Company to plug at: Hour: 9 a.m. Day: 7 Month: 11 Year: 19 89

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-356-1237

were: 7" at 6109' PBD 5726' Perfs at 4810-14, 4816-26, 5516-27, 5546-50'
Packer stuck at 5485', tubing in to at 2948'

1st plug pump 30 sx cement at 2 sx hulls to 4800', 2nd plug CIBP at 2924' with 2 sx cement,
Spot through casing:
3rd plug at 2400' with 50 sx cement, 4th plug at 1940' with 50 sx cement,
5th plug at 600' with 50 sx cement, 6th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 8 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement and 2 sx hulls to 4800',
2nd plug set CIBP at 2924' with 2 sx cement on top, Spotted through casing:
3rd plug at 2400' with 50 sx cement,
4th plug at 1940' with 50 sx cement,
5th plug at 600' with 50 sx cement,
6th plug at 40' with 10 sx cement.

Remarks: Used common cement by Midwest Casing Pulling. Recovered 2430' of 7" casing.
(if additional description is necessary, use BACK of this form.)

~~I did not observe this plugging.~~

Signed Richard M. Lacey
(TECHNICIAN)

DATE 11-15-89

FILE NO. 26445

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1989
11-13-89
CONSERVATION DIVISION
WICHITA, KANSAS