

To: 1 070032  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,457 - 0000  
C NE SE , SEC. 15 , T 32 S, R 38 W  
1980 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5952  
Operator: Amoco Production Company  
Name & Address: P. O. Box 432,  
Liberal, KS 67901

Lease Name Edna Scott Well # 3  
County Seward 195.00  
Well Total Depth 6000 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1616

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling License Number 6497  
Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 10:00 am Day: 18 Month: October Year: 19 85

Plugging proposal received from Ed Eves  
(company name) Midwest (phone) 316-675-8349

were: 5 1/2" at 6000' PBD 5948' Perfs at 5780-5792 Pump through 5 1/2" with mud between  
1st plug set CIBP at 5700' with 2 sx cement plugs

2nd plug on stub with 50 sx cement

3rd plug at 1676 with 50 sx cement

4th plug at 720 with 40 sx cement  
solid bridge - hulls - plug at 40' --

5th plug cement to surface Plugging Proposal Received by Dan Goodrow  
with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 5:00 pm Day: 18 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2530' with 50 sx cement, 2nd plug at 1676' with 50 sx  
cement, 3rd plug at 720' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 10 sx cement

Remarks: Recovered 2530' 5 1/2" casing. Used Common Cement by Midwest.  
(if additional description is necessary, use BACK of this form.)  
Richard W. Lacey observed the plugging  
(did not observe this plugging.)

DATE OCT 29 1985  
INV. NO. 10764

RECEIVED  
STATE CORPORATION COMMISSION  
10-28-85  
OCT 28 1985

Signed Dan Goodrow  
(TECHNICIAN) P.A.S.