

To: 1 060984  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,309-0000  
SE SW, SEC. 15, T 32 S, R 33 W/E XX  
660 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952  
Operator: Amoco Production Company  
Name &  
Address P.O. Box 432  
Liberal, KS 67901

Lease Name Hattie Jones Well # 1  
County Seward 165.75  
Well Total Depth 5100 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1586

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling License Number 6497  
Address Box F, Sublette, KS 67877

Company to plug at: Hour: 11 a.m. Day: 21 Month: 7 Year: 19 87

Plugging proposal received from Ed Eves

(company name) Midwest Casing Pulling (phone) 316-675-8349

were: 5 1/2" at 5100' PBSD 4844' Perfs at 4758-63, 4766-72'

1st plug set CIBP at 4710', 2nd plug at 2610' with 50 sx cement,  
3rd plug at 1600' with 50 sx cement, 4th plug at 800' with 35 sx cement,  
5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 23 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4710'

2nd plug at 2610' with 50 sx cement,

3rd plug at 1600' with 50 sx cement,

4th plug at 800' with 35 sx cement,

5th plug at 40-0' with 10 sx cement.

Remarks: Used common cement by Midwest Casing Pulling. Recovered 2615' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

(If additional description is necessary, observe this plugging.)

Signed Paul G. Luthi  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 24 1987

CONSERVATION DIVISION  
Wichita, Kansas

7-23