

153
R

To: 1 092117
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,050-0000
C S/2 NW, SEC. 5, T 32 S, R 33 W/E
3300 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: Box 351
Liberal, KS 67901

Lease Name Morgan Well # 2-5
County Seward 87.26
Well Total Depth 2685 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 567

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 3 p.m. Day: 7 Month: 4 Year: 19 88

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 2684' PBD 2602' Perfs at 2574-97, 2542-47'
1st plug pump 20 sx cement on bottom,
2nd plug pump 40 sx cement at cut off,
3rd plug pump 40 sx cement at 8 5/8" at 567',
4th plug pump 10 sx cement at top.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 9 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement, pressured up at 2597-2350,

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1988

2nd plug pumped 20 sx cement at 1300'-1100',
Shot casing at 1017' and 601' and couldn't pull,
3rd plug shot off at 540' and pumped 60 sx cement,
4th plug pumped 10 sx cement at 40-0'.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 540' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

(did ~~xxxxxx~~) observe this plugging.

Signed Glenn R. Barlow
(TECHNICIAN)

DATE 4-27-88
20477
4-9