

To: 1 000753
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-175-00252-0000
API NUMBER 15- Drill Date 1/4/58
C SW NE, SEC. 6, T 32 S, R 33
3324 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 4549
Operator: Anadarko Petroleum Corporation
Name: Anadarko
Address: P.O. Box 351
Liberal, KS 67905-0351

Lease Name Ellis Well / 1-6
County Seward
Well Total Depth 2670 86.77 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 600

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 10:30 a.m. Day: 31 Month: 5 Year: 19 94

Plugging proposal received from Doug Blair
(company name) Sargent's Casing Pulling (phone) 316-624-7455

Perfs: 4 1/2" at 2660' w/175 sx cement, PBTD 2639', Perfs at 2485-2500, 2513-74, 2591-2618'
1st plug pump 2 sx hulls and 25 sx cement from 2618-2300',
2nd plug load hole with mud and pump 20 sx cement at 1400' with tubing.
3rd plug pump 40 sx cement at 620',
4th plug pull tubing and fill 4 1/2" X 8 5/8" to surface.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:10 p.m. Day: 6 Month: 6 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at 2618-2300',
2nd plug loaded hole with mud and pumped 20 sx cement at 1400' with tubing,
3rd plug pumped 40 sx cement at 620',
4th plug pulled tubing and filled 4 1/2" X 8 5/8" to surface.
Perforated pipe at 638' and 520'. Could not pump into.

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1994

Remarks: Used common cement by Sargent's. No casing recovery.
(If additional description is necessary, use BACK of CONSERVATION DIVISION
Wichita, Kansas.)

Signed Glenn R. Barlow (TECHNICIAN)

I (did / ~~XXXXXX~~) observe this plugging.
6-14-94
40565
6-6